



Reliable Engineers & Associates

No. 4/19, Kamatchi Amman Koil West Street,
 " Sri Sai Anugraha Nivas " IIInd Floor,
 Sengunthapuram, KARUR - 639 002.
 Phone : 04324 - 274070
 Mobile : 9942515890, 9965130162.

Ref :

Date :

TO :-

Rotary club of Karur Texcity
 Karur,

Dear sir ; Submission of Quotation for Renovation of Existing toilet for Girls students and construction of new Toilets at Kulathupalayam Government Elementary School , Karur.

Cost Estimation For Two Toilets With Urinals

S.I No	Description	Unit	Total Qty	Rate / Unit in Rs.	Amount in Rs.	Remarks
1	Earth work Excavation	Cft	203.25	7	1,433.00	
2	P.C.C 1:5:10	Sqft	107.63	30	3,229.00	
3	R.R Masonary in C.M 1:6	Cft	371.12	48	17,814.00	
4	Brick work in C.M 1:6	Sqft	535.13	95	50,837.35	
5	Plinth Filling	Cft	258	5	1,290.00	
6	Floor P.C.C 1:4:8	Cft	149.5	35	5,233.00	
7	Lintel R.C.C concrete 15 Concrete with Reinforcement & centering	Cft	28.13	400	11,252.00	
8	PPL Sheet Roofing	Sqft	200	122	24,400.00	
9	Inside & Outside plastering	Sqft	900	18	16,200.00	
10	Antiskid Floor Tiles	Sqft	160.75	60	9,645.00	
11	Wall Tiles	Sqft	204	58	11,832.00	
12	Step Tiles	Sqft	14	90	1,260.00	
13	Jally (R.C.C) for Ventilator	Nos	7.92	55	436	
14	Indian Type Water Closset	Nos	2	1600	3,200.00	
15	Fixing of Sink	Nos	11	-	2,000.00	

B/F

Reliaable Engineerrrs & Associates

16	Ceramic hall round / Pvc	L.s			1,800.00
17	Connection to S.P.T	L.s			2,000.00
18	Plumping works inlet & wall greeting etc..	L.s			11,000.00
19	Pvc Door fixing 2' 3" x 7'	Nos	2	1650	3,300.00
20	Steel Gate	Sqft	28	130	3,640.00
21	Courwashing	Sqft	900	9	8,100.00
	Un forceen items				2,957.00
	Total Amount - C				<u>1,92,858.00</u>

Rebate for Annexturing the existing Toilet Rs.15,068/- (-) Rs.15,068/-

Net Value of the Construction Cost Rs.1,77,790.00 - C

Hence the Total construction cost

Total Amount (A+ B + C)

Rs.3,50,000/-

(55,210 + 1,17,000 + 1,77,790)


(Rupees Three Lacks Fiffy Thousands Only)

Thanking You ,

Date : 02.11.11

Place : Karur

Yours Faith Fully ,


(P. Mohan)



Reliaable Engineerrrs & Associates

No. 4/19, Kamatchi Amman Koil West Street,
 * Sri Sai Anugraha Nivas * IIInd Floor,
 Sengunthapuram, KARUR - 639 002.
 Phone : 04324 - 274070
 Mobile : 9942515890, 9965130162.

Ref :

Date :

To :

Rotary Club of Karur Angels,
 Karur.

S.I NO	Description	Unit	Qty	Rate	Amount
1	Brick work in Cement mortar	Cft	163	130	21190 /-
2	Reinforcement Brick wall	Sft	39.96	260	10389.6 /-
3	Plastering work in Cement mortar	Sft	493.62	20	9872.4 /-
4	Repairing the cracks with Necessary Chemicals	Sft	100	25	2500 /-
5	Water supply line 3/4" dia pipe 15kg	Feet	45	35	1575 /-
	1" dia pipe 15kg	Feet	45	45	2025 /-
6	3/4" Gate valve	Nos	2	480	960 /-
7	1/2" C.P Taps	Nos	10	450	4500 /-
8	Providing and instaling 500 lit cap. Pvc tank with necessary fittings	Nos	1	5000	5000 /-
9	White and colour washing inner	Sft	1069	10	10690 /-
10	Outer Colour washing with Cem	Sft	1369	10	13690 /-
11	painting for Steel Doors with Ennammel paint	Sft	142.46	16	2279.36 /-
12	Roofing with PPL Sheet	Sft	250	122	30500 /-
	Cleaning the Site				1829 /-

Total Amount A

Rs. 1,17,000.00



Reliaable Engineerrrs & Associates

No. 4/19, Kamatchi Amman Koil West Street,
" Sri Sai Anugraha Nivas " IIInd Floor,
Sengunthapuram, KARUR - 639 002.
Phone : 04324 - 274070
Mobile : 9942515890, 9965130162.

Ref :

Date :

a.	Floor Tiles	Sft	390	65	25350 /-
b.	Wall Tiles	Sft	276	65	17940 /-
c.	Skirting Tiles	Rft	44	55	2420 /-
d.	Urinal Channel makking	Rft	40	50	2000 /-
e.	Wash Basin with Necessary Fittings	Nos	3	2500	7500 /-

Total Amount B

Rs. 55,210/-